

INDIAN INSTITUTE OF MANAGEMENT NAGPUR
Tender No : IIMN/CAO/15/2018-19 dated 10/12/2018



Name of Work: Supply, Installation Testing and Commissioning of Split Air conditioners for library & Faculty offices

Name of bidder:

Price bid part-II

Sr.no	Description	Qty	Unit	Rate	Rate in words	Amount
1	Supplying, installation, testing and commissioning of following capacity Hyper Tropical wall mounted Split Type Air Conditioner with remote having rotary compressor, machine designed upto 52 deg .C.with advance filters, operating on refrigerent-410 A, for 230 V 50 Hz single phase A/C supply, capable of performing the function as cooling, dehumidifying, air circulation i/c all standard accessories and MS stand for outdoor unit with following capacity cooling etc complete as required.					
	a)2.0 TR (3 star) Toshiba-RAS-24S3KS-IN +RAS-24S3AS-IN(OR Similar Make in O general model OR Mitsubishi OR DAIKIN	4	No			
	b)1.1 TR (5 Star)(Make:Toshiba Inverter Split AC Model:RAS-13N3KCV-IN or similar in Diakin/Mitsubishi/O General)	7	No			

Sr.no	Description	Qty	Unit	Rate	Rate in words	Amount
2	Supplying and fixing of Extra copper piping of size 5/8" and 1/4" with nitrile rubber insulation from indoor unit to outdoor unit of 2 TR with all accessories etc. complete as required.	30	MTR			
3	Supplying and fixing of Extra copper piping of size 3/8" and 1/4" with nitrile rubber insulation from indoor unit to outdoor unit of 1.0 TR with all accessories etc. complete as required.	30	MTR			
4	Supplying and fixing of 3 core 4 sq.mm. PVC insulated PVC sheathed copper conductor cable on surface of wall/ceiling for connection between indoor & Outdoor unit required.	40	MTR			
5	Supplying, Installation, Testing and commissioning of UPVC drain Piping of following sizes with adequate supports as per specifications and instructions of Engineer-in charge.(a) 25 mm dia (Plasto, Finolex,Supreme)	30	MTR			
6	Supplying and fixing of 3 core 4 sq.mm. PVC insulated unarmoured copper conductor cable for indoor to outdoor PCB supply confirming to confirming to IS:1554(Part-1) on surface etc. complete as required. (Finolex/Rrcable/Havells)	30	MTR			
7	Shifting of Existing AC's to new location including all necessary accaroires , gas refilling & Labour etc complete.					
a	1.1 TR (Toshiba make)	1	No			

Sr.no	Description	Qty	Unit	Rate	Rate in words	Amount
b	1.5 TR (Toshiba Make)	1	No			
8	Providing & Fixing 12 mm Plywood for fixing & Mounting of split AC unit. Including all necessary hardware material & labour etc complete.	4	Sq.m			
				Total Amount		
				Add % GST		
				Grand Total		

Note:

- 1 All rates are to be quoted excluding the GST applicable. The GST will be paid in addition to the total amount payable.
- 2 The above quantity may vary as per actual requirement of Site.