



Name of Work: Provision of Hand wash Basin &amp; various miscellaneous works at hostel A , B &amp; E block for IIM Nagpur.

IIM NAGPUR

## Part-II- Price Bid

Bidder Name						
Sr.no	Particulars	Quantity	Unit	Rate	Rate in Words	Amount (Rs.)
1	Providing and fixing white glazed earthenware Wash Hand Basin of 55cm. x 40 cm. size including cold water pillar tap brackets, rubber plugs and , stop tap and necessary pipe connections including P.V.C. waste pipe and trap up to the outside face of the wall. Making good the damaged surface, testing etc. complete.	16.00	No			
2	Providing and fixing 450mm x 550mm size superior type Belgium mirror etc. complete.	16.00	No			
3	Providing and fixing chromium plated towel rod 16 mm dia and 75 cm. in length including all accessories complete.	16.00	No			
4	Providing and fixing on walls/ ceiling/ floor 15 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc.complete. Including removing existing pipe line if necessary as directed etc.complete.	40.00	RMT			
5	Providing and fixing on walls/ ceiling/ floor 40 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc.complete. Including removing existing pipe line if necessary as directed etc.complete.	40.00	RMT			
6	Providing and fixing Glass self 125 mm wide and 600 mm long with necessary chromium plated brackets providing T.W.gutties etc. complete	16	No's			

Sr.no	Particulars	Quantity	Unit	Rate	Rate in Words	Amount (Rs.)
7	Providing and fixing C.P two way bib cock with wall flange and health foucet with 1 meter long pvc tube and wall hook of approved quality .	7	No			
8	Providing and fixing 15cm x 10cm salt glazed stoneware gully trap in cement concrete 1:4:8 outside the building including cast iron grating in the sink, connecting glazed stoneware pipe, brick masonry chamber with cast iron lid and cast iron grating for the gully trap.	3	No's			
9	Providing and constructing Brick Masonry Inspection Chamber 60cm x 45cm x 90cm including Excavation,1:4:8 cement concrete foundation 1:2:4 cement concrete channels half round G.S.W. pipes, Brick Masonry, plastering from inside and with frame fixed in cement concrete with R.C.C. Cover medium duty 140 kg with frame etc complete.	1	No's			
10	Providing, laying and fixing P.V.C. pipe of 110 mm. dia. with fittings such as bends, tees, reducers, clamps, etc. including necessary excavation, trench filling etc. complete. Including removing existing pipe line if necessary and as directed etc. complete.	20	Rmt			
11	Providing and fixing P.V.C. pipes of 160mm outer diameter and having wall thickness of 2.2 to 2.7 mm confirming to I.S. 13592- 1992 including proper stromwater receiving recess with P.V.C. plug, bend, necessary fittings, such as, offsets, shoes ,filing the joint using rubber gasket with solvent cement and , including necessary scaffolding ,all the P.V.C. fittings and excavation	13	Rmt			

Sr.no	Particulars	Quantity	Unit	Rate	Rate in Words	Amount (Rs.)
12	Providing water proof bedding for flooring of U.G Sump 25 mm thick in C.M. 1:3 including using approved water proofing compound in specified proportion as per manufacturers specifications for per bag of cement including leveling, curing and including ponding test etc. complete.	30.05	Sq.m			
13	Providing and fixing C.P. pillar cock long neck with aerator of approed make including necessary sockets/union nut etc. complete.	10	NO's			
14	Providing and fixing 40 mm. dia Ball cock medium type with PVC float including sockets and necessary fittings and tested as per requirements etc. complete.	2	NO's			
15	Removing and refixing of existing paving block with necessary levelling , Sand dust.	50	Sq.m			
	<b>Total</b>					
	<b>ADD % GST</b>					
	<b>GST Amount</b>					
	<b>Grand Total</b>					
Note:	1.All rates are to be quoted excluding the GST applicable. The GST will be paid in addition to the total amount payable.					
	2.The above quantity may vary as per actual requirement of Site.					