

INDIAN INSTITUTE OF MANAGEMENT NAGPUR

IIMN/EM&ES/13/2022-23 dated 30-03-2023

Name of work: Provision of Acoustical Wall panelling and carpet for making Studio on the First floor of the admin block at IIM Nagpur

Part-II- Price Bid (separate sealed Envelope)

Name of Bidder :

Sr. No	Description	Qty	Unit	Rate	Amount
1	Providing and fixing Fabric in wall panelling over aluminum frame and MDF board as ISI marked IS : 14842, plain lining with necessary glass wool, screws on the exposed surface, etc., complete as per the instruction of Engineer-Incharge. (50mm Framing+12mm MDF+06mm MDF+Fabric in one side) As per the colour / Shade made in the Academic block	19.0	Sq.m		

Signature of bidder with seal

Sr. No	Description	Qty	Unit	Rate	Amount
2	Providing and fixing 1mm laminate in wall panelling over an aluminum frame and MDF board as ISI marked IS: 14842, plain lining with necessary glass wool, screws on the exposed surface, etc., complete as per the instruction of the Engineer-Incharge. (50mm Framing+12mm MDF+06mm Plywood +1 mm laminate side) laminate as per the existing shade/colour in the Academic block	7.0			
3	Providing and fixing Acoustical wooden wall panelling over aluminum frame and MDF board as ISI marked IS : 14842, plain lining with necessary glass wool, screws on the exposed surface, etc., complete as per the instruction of Engineer-Incharge. (50mm Framing+12mm MDF+06mm MDF+ Acoustical wooden panel in one side) As per the sample made in the Academic block (As per existing wooden wall shade/colour in academic block)	7.0	Sq.m		

Sr. No	Description	Qty	Unit	Rate	Amount
4	Providing & Pesting Carpet Tiles of more than 800+ gsm, made with 100% stain-proof fibers of approved make along with 5mm underlay as per Architectural & Acoustical Design & Instructions & Complete in all aspects including all materials labour, finishing, etc., complete 8mm thick Ecosphere Glacier with Colorbeat electric Orange Carpet of Make-Mohak all complete as per the direction of Engineer In Charge. As per the sample available in the Estate maintenance department.	30	Sq.m		
5	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. Angle 50X50X6mm fixed with anchor bolt in Existing Beam	20	Kg		
	Toral Amount				
	GST Percentage (%)				

Note: 1.All rates are to be quoted excluding the GST applicable. The GST will be paid in addition to the total amount payable.

2.The above quantity may vary as per actual requirement of Site.

Signature of bidder with seal